Your Company Here
100 Main St, Your City, ST 00000
(555) 555-0100
estimates@yourcompany.example

RAPID SQUARES

401 Garrison St, Bulpitt, IL 62517, USA



MEASUREMENTS	
Roof area	3,595 sq ft
Squares	35.95
With 10% waste	39.67
With 12% waste	40.33
With 15% waste	41.67
Footprint	3,430 sq ft
Perimeter	455 ft
Buildings	4
Ordered	November 10, 2026

Squares by Pitch

What each building measures at every pitch, from its footprint, and the squares to order with common wastes. Our estimate is highlighted.

Building	Waste	1/12	2/12	3/12	4/12	5/12	6/12	7/12	8/12	9/12	10/12	11/12	12/12
1 Structure 1	Measured	17.64	17.82	18.12	18.53	19.05	19.66	20.35	21.13	21.98	22.88	23.85	24.86
Our pitch 4/12	+10%	19.67	19.67	20.00	20.67	21.00	21.67	22.67	23.33	24.33	25.33	26.33	27.67
1,758 sf footprint	+12%	20.00	20.00	20.33	21.00	21.33	22.33	23.00	23.67	24.67	25.67	27.00	28.00
183 ft perimeter	+15%	20.33	20.67	21.00	21.33	22.00	22.67	23.67	24.33	25.33	26.33	27.67	28.67
2 Structure 2	Measured	7.04	7.11	7.23	7.40	7.60	7.84	8.12	8.43	8.77	9.13	9.52	9.92
Our pitch 3/12	+10%	8.00	8.00	8.00	8.33	8.67	8.67	9.00	9.33	9.67	10.33	10.67	11.00
702 sf footprint	+12%	8.00	8.00	8.33	8.33	8.67	9.00	9.33	9.67	10.00	10.33	10.67	11.33
107 ft perimeter	+15%	8.33	8.33	8.33	8.67	9.00	9.33	9.67	10.00	10.33	10.67	11.00	11.67
3 Structure 3	Measured	8.28	8.36	8.50	8.70	8.94	9.22	9.55	9.92	10.31	10.74	11.19	11.67
Our pitch 4/12	+10%	9.33	9.33	9.67	9.67	10.00	10.33	10.67	11.00	11.67	12.00	12.33	13.00
825 sf footprint	+12%	9.33	9.67	9.67	10.00	10.33	10.33	11.00	11.33	11.67	12.33	12.67	13.33
116 ft perimeter	+15%	9.67	9.67	10.00	10.33	10.33	10.67	11.00	11.67	12.00	12.67	13.00	13.67
4 Structure 4	Measured	1.46	1.47	1.50	1.53	1.57	1.62	1.68	1.74	1.81	1.89	1.97	2.05
Our pitch 3/12	+10%	1.67	1.67	1.67	2.00	2.00	2.00	2.00	2.00	2.00	2.33	2.33	2.33
145 sf footprint	+12%	1.67	1.67	2.00	2.00	2.00	2.00	2.00	2.00	2.33	2.33	2.33	2.33
49 ft perimeter	+15%	2.00	2.00	2.00	2.00	2.00	2.00	2.00	2.33	2.33	2.33	2.33	2.67

Measured from imagery: verify on site before ordering material. Waste rows are rounded up to the next bundle (a third of a square).